

# Star Ledger Montville Facility Truck Loading Docks and Pavement Modifications



## Design Data

### Owner

The Star Ledger

### Location

Montville, New Jersey

### Project Cost

\$650,000.00

### Project Features

- Power Roll-up Doors
- Dock levelers
- Trench Drain System
- Grass Pavers
- Widened Travel Lanes
- Concrete Truck Apron
- 45,000 square feet of asphalt paving for truck parking



PCI designed architectural, electrical, and soil erosion and sediment control plans involving the renovations of one loading dock facility and the installation of a new loading dock area at the Star-Ledger newspaper printing and distribution plant in Montville. Our staff oversaw work involving the upgrading of the existing loading dock leveler stations, including the replacement of worn concrete with freshly-poured concrete in the dock leveler pits, the installation of modernized dock levelers, electrical apparatus, and traffic control devices such as bumper guards and bollards, and the establishment of bases, forms, and laying of concrete and asphalt for truck driveway entrance for one of the renovated loading dock areas.



PCI  
Professional Consulting, Inc.

Consulting Engineers